

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31191
Name: R&B Oil & Gas, Inc
Address 1: 124 N Main
Address 2: PO Box 195
City: Attica State: KS Zip: 67009 + 9217
Contact Person: Randy Newberry
Phone: (620) 254-7251
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Indian Depth to Top: 2354 Bottom: 2490 T.D. 2500
Cave Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 095-21788-00-00
Spot Description: C W/2 NW NW
NW NW NW Sec. 12 Twp. 30 S. R. 9 East West
600 Feet from North / South Line of Section
310 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kingman
Lease Name: Adelhardt Well #: 2
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Jeff Klock (KCC District Agent's Name)
Plugging Commenced: 12/7/11
Plugging Completed: 12/12/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	231	200 Sacks Cement
Indian Cave	Gas	Production	4.5	2499	100 Sacks Cement

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Checked hole, sand at 2320'; bailed 4 sacks cement on sand. Ripped casing at 1860', pipe came free. Pulled casing to 1250' & pumped 35 sacks cement, 3%cc & 100# hulls. Pulled to 900' & pumped 35 sacks cement, 3%cc & 100# hulls. Pulled to 280' & circulated with 90 sacks cement to surface. Pulled rest of casing.

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc
Address 1: 190 U S Hwy 45 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-3410

Name of Party Responsible for Plugging Fees: R&B Oil & Gas, Inc.
State of Kansas County, Harper, ss.
Randy Newberry Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Randy Newberry

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
FEB 24 2012
KCC WICHITA

QUALITY WELL SERVICE, INC.

5338

Home Office 324 Simpson St., Pratt, KS 67124

Todd's Cell 620-388-5422
Office / Fax 620-672-3663

Rich's Cell 620-727-3409
Brady's Cell 620-727-6964

Date	12-12-11	Sec.	12	Twp.	30	Range	9	County	Kingman	State	KS	On Location		Finish	500
Lease	Adelhardt		Well No.	2		Location									
Contractor						Owner									
Type Job						To Quality Well Service, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.									
Hole Size						T.D.									
Csg.						Depth									
Tbg. Size						Charge To									
Tool						Street									
Cement Left in Csg.						City									
Meas Line						State									
Shoe Joint						The above was done to satisfaction and supervision of owner agent or contractor.									
Displace						Cement Amount Ordered									
EQUIPMENT						160.5x 160/40 4%									
Pumptrk	8	No.	David			Common									
Bulktrk	4	No.	m.ke			100									
Bulktrk		No.				Poz. Mix									
Pickup		No.				60									
JOB SERVICES & REMARKS						Gel.									
Rat Hole						2									
Mouse Hole						Hulls									
Centralizers						200 #									
Baskets						Salt									
D/V or Port Collar						Flowseal									
1 st pumped 35cks 3%cc 100 # hulls @ 12.50'						Koi-Seal									
2 nd pumped 35cks 3%cc 100 # hulls @ 900'						Mud CLR 48									
3 rd pumped 90cks @ 280' to surface						CFL-117 or CD110 CAF 38									
						Sand									
						Handling									
						168									
						Mileage									
						45									
						FLOAT EQUIPMENT									
						Guide Shoe									
						Centralizer									
						Baskets									
						AFU Inserts									
						Float Shoe									
						Latch Down									
						Pumptrk Charge									
						Plug									
						Mileage									
						45									
						Tax									
						Discount									
						5%									
						Total Charge									
Signature															

RECEIVED
FEB 24 2012

KCC WICHITA