

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30253
Name: Cyclone Petroleum, Inc.
Address 1: 1030 W Main
Address 2: _____
City: Jenks State: OK Zip: 74073 + _____
Contact Person: James Haver
Phone: (918) 291-3200
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Miss Depth to Top: 3200 Bottom: 3460 T.D. 3350
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 079206870000
Spot Description: _____
SW NW NE SE Sec. 29 Twp. 22 S. R. 3 East West
2,280 Feet from North / South Line of Section
1,110 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Harvey
Lease Name: BB Well #: 29-1
Date Well Completed: August 23, 2011
The plugging proposal was approved on: Dec. 09, 2011 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: Jan. 25, 2012
Plugging Completed: Jan. 25, 2012

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Surface	Fresh Water	Surface	13.375	262	none
Miss	Oil, Gas & Brine	Production	4.5	3807	280 ft.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded off perfs and bailed 4 sacks of cement to plug bottom. Tagged bottom plug @ 3150. Pulled 280 ft. of production casing. Ran tubing in well and placed 35 sack plug at 545 ft. Pulled tubing up to 260 ft. Pumped cement down tubing and circulated good cement to surface. Pulled all tubing. Filled up hole with cement. Plugging witnessed by KCC rep. BJ Hope.

Plugging Contractor License #: 8253 Name: G & L Well Service
Address 1: 612 E Washington Address 2: _____
City: Sterling State: KS Zip: 67579 + _____
Phone: (620) 278-2703
Name of Party Responsible for Plugging Fees: Cyclone Petroleum, Inc.
State of Okla. County, Tulsa, ss.
Larry Ressler Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
FEB 27 2012
KCC WICHITA 