

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 34148 Name: Sabco Oil & Gas Co. Address 1: 34 Wynden Dr. City: Houston State: TX Zip: 77056 Contact Person: Max Jameson Phone: (713) 595-3612 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API No. 15 - 151-22356-00-00 Spot Description: NW SE SE NE Sec. 28 Twp. 27 S. R. 12 East West 2010 1982 Feet from North South Line of Section 33+ 358 Feet from East West Line of Section GPS-KCC Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Pratt Lease Name: Bergner Well #: 1-28 Date Well Completed: The plugging proposal was approved on: (Date) by: Steve Peifer (KCC District Agent's Name) Plugging Commenced: 2/15/12 Plugging Completed: 2/17/12

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows show casing sizes of 8-5/8" and 5-1/2" with corresponding depths and pulled out measurements.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set BP @ 3700', dumped 2sx common on BP with bailer. Pulled stretch, got 19" of stretch. Cut casing @ 2590'. Pulled casing to 2470', full of oil. Pumped 50bbls of saltwater to kill well. Pulled casing up to 900', pumped 15sx gel 50sx 60/40poz 4% gel. Pulled to 400', pumped 60sx 60/40poz. Pulled to 40', pumped 40sx 60/40poz. Cement didn't circulate. Ran bailer, hit cement @ 120'. Filled up surface with 35sx 60/40poz. Plugging complete.

Plugging Contractor License #: 31529 Name: Mike's Testing and Salvage Inc Address 1: PO Box 467 Address 2: City: Chase State: KS Zip: 67524 Phone: (620) 938-2943 Name of Party Responsible for Plugging Fees: Sabco Oil and Gas State of KS County: Rice, ss. Mike Kelso (Print Name) Employee of Operator or Operator on above-described well.

RECEIVED FEB 28 2012

KCC WICHITA

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Handwritten Signature]

AL