

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34470
Name: Victory Minerals LLC
Address 1: P O Box 414931
Address 2: _____
City: Kansas City State: MO Zip: 64141 + _____
Contact Person: Carmon Decker
Phone: (816) 223-3712
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 2940 Bottom: 3100 T.D. 3100
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 035-22895 • 00 • 00
Spot Description: SE-NW-SW
SE NW SW Sec. 32 Twp. 33 S. R. 6 East West
1,730 Feet from North / South Line of Section
1,085 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Cowley
Lease Name: Berry Well #: 9
Date Well Completed: September 11, 1981
The plugging proposal was approved on: 1-16-2012 (Date)
by: Jeff Klock (KCC District Agent's Name)
Plugging Commenced: 2-27-2012
Plugging Completed: 2-27-2012

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	200	0
Mississippi 2940-3100	oil and water	Long string	4.5	3100	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Cornish Wireline Services shot two holes at 350'. Sam's Well Service ran in 2 & 3/8" tubing with jagged edge cut collar on bottom of tubing and hit steel at 319' on February 24. Called Duane Krueger to inform him of well status and set a time to plug Monday February 27th. Copeland tried to circulate and drill through bridge, went outside of casing, parted casing. Received KCC permission to plug at 314'. Copeland Acid and Cement pumped in and circulated cement to surface in 4.5" and also to surface in surface casing. Pulled 2", filled casing with cement, surface remained full. Filled 4.5 to surface again on 2-28-12. Cut off surface and casing and filled hole around well head. Copeland Acid and Cement ticket # 38016, used 180 sacks of 60/40/4.

Plugging Contractor License #: 34470 99998 Name: Victory Minerals LLC
Address 1: P O Box 414931 Address 2: _____
City: Kansas City State: MO Zip: 64141 + _____
Phone: (816) 223-3712
Name of Party Responsible for Plugging Fees: Victory Minerals LLC
State of Kansas County, Cowley, ss.
Carmon Decker Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Carmon Decker

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 05 2012
KCC WICHITA