

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 34546 Name: KLABZUBA OIL & GAS, INC Address 1: 700 17TH ST, STE 1300 Address 2: City: DENVER State: CO Zip: 80202 Contact Person: BRETT WISNER Phone: (303) 299-9097

Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API No. 15 - 15-051-26251-00-00

Spot Description: SW NW NE SW Sec. 2 Twp. 13 S. R. 20 East West 2,135 Feet from North South Line of Section 1,600 Feet from East West Line of Section

Footages Calculated from Nearest Outside Section Corner: NE NW SE SW

County: ELLIS

Lease Name: DORZWEILER TRUST Well #: 2-11-13-20

Date Well Completed: 3/2/12

The plugging proposal was approved on: 3/1/12 (Date)

by: RAY DINKEL (KCC District Agent's Name)

Plugging Commenced: 3/1/12

Plugging Completed: 3/2/12

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: SURFACE, 8 5/8, 263, 0.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 230 sacks total of 60/40 Poz, 4% gel, 1/4# flo-seal, 1st plug @ 3862' with 25 sacks, 2nd plug @ 1520' with 25 sacks, 3rd plug @ 736' with 100 sacks, 4th plug @ 313' with 40 sacks, 5th plug @ 40' to surface with 10 sacks, and 30 sacks for rat hole, by Consolidated (Ticket #33890), job was complete @ 1:30 am on 3/2/2012.

Plugging Contractor License #: 33350 Name: SOUTHWIND DRILLING, INC

Address 1: 8 NORTH MAIN Address 2: PO BOX 276

City: ELLINWOOD State: KANSAS Zip: 67526

Phone: (620) 564-3800

Name of Party Responsible for Plugging Fees: KLABZUBA OIL & GAS, INC

State of KANSAS County, BARTON, ss.

JILL WAHLMEIER (Print Name) Employee of Operator or Operator on above-described well.

being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jill Wahlmeier

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED MAR 07 2012 KCC WICHITA



Southwind Drilling, Inc.
Plugging Orders & Reports

Lease: Dorzweiler Trust

Plugging Received from KCC Representative:

Name: Ray Dinkle Date: 3-1-12 Time: 11:30 AM

1 st plug @ <u>3862</u> feet, <u>25</u> sacks	Stands <u>62</u>
2 nd plug @ <u>1520</u> feet, <u>25</u> sacks	Stands <u>24</u>
3 rd plug @ <u>736</u> feet, <u>100</u> sacks	Stands <u>11 1/2</u>
4 th plug @ <u>313</u> feet, <u>40</u> sacks	Stands <u>4 1/2</u>
5 th plug @ <u>40</u> feet, <u>10</u> sacks	Stands <u>1 JT</u>

Mousehole: 2 sacks

Rathole: 30 sacks

Total Cement Used: 230 sacks

Type of cement: 60/40 Poz 4% Gel 44# Flo Seal

Plug Down @ 3-2-12 1:30 AM

Call KCC When Completed:

Name: Rich Williams Date: 3-2-12 Time: 2:00 PM

RECEIVED
MAR 07 2012
KCC WICHITA