

15-169-00834, -00-00

12
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
8-22-61
AUG 22 1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Saline

Location: N7- N7- NE- Sec. 32 Twp. 15 Rge. 3 (W) (W)

Name of Field: Unknown Total Depth: 3381'

I have this date completed supervision of plugging of:

Lease Name: Ahlstedt Well No. I

Operator's Full Name: Currier & Keys

Complete Address: Arcade Bldg. Salina Kansas.

Plugging Contractor Knight Casing Pulling Co.

Address: Box 304, Chase Kansas. License No. 436

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 6:PM Day 9 Month 8 Year 61

The above well was plugged as follows:

Filled hole w/ sand from T.D. 3381' back to 3365' ran 5 sax cement w/ dump bailer.

Shot off and pulled 5-1/2" casing. Filled hole w/ mud from 3315' back to 240' set a 10'

Rock bridge and 20 sax cement. Filled hole w/ mud from 170' back to 35' set a 5' rock

bridge and 8 sax cement back to zero. 8-5/8" surface pipe 3' below ground level.

Signed: William Jones
Conservation Division Agent

Reviewed: Geahan Harold Hollis
Field Supervisor

Remarks:

INVOICED

DATE 8/31/61

INV. NO. 3656-W