

15-101-20052-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1973
02-20-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Donald C. Slawson,
Complete Address 408 One-Twenty Building, Wichita, Kansas.
Lease Name Carter Well No. E-2
Location W/2-E/2-W/2- Sec. 1 Twp. 16 Rge. (E) (W) 27
County Lane Total Depth 2115'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Slawson Drilling Company, Incorporated,
Address 408 One-Twenty Bldg., Wichita, Ks. License No.
Operation Completed: Hour 1:15 AM Day 16 Month 2 Year 1973

The above well was plugged as follows:

299'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 600'.

Circulated hole with heavy mud. Pulled DP to 825' and displaced 110 Cu. Ft. cement
thru DP from 825' to 500'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 2/22/73
INV. NO. 7020-W