

15-101-00066-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1964
03-20-1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pet-Ex Company,

Complete Address: 702 Union Center Building, Wichita, Kansas.

Lease Name Curtis Well No. 1

Location CNW-NE Sec. 1 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 4510

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Hellar Drilling Company, Incorporated,

Address: 1014 Union Center Bldg., Wichita, Kansas. License No. _____

Operation Completed: Hour 5:30AM Day 14 Month 3 Year 1964

The Above well, was plugged as follows:

258'--8 5/8" Surface pipe, cement circulated with 200 Sx.
Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx cement
thru DP. Heavy mud to 240', set plug with 1/2 sack hulls and displaced 20 Sx.
cement thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/20/64
INV. NO. 8831-W

Signed: W. L. Nichols
Well Plugging Supervisor