

15-101-19006-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 1 - 1972
05-01-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Anderson Well No. J-1

Location NE-SE-NW Sec. 23 Twp. 16 Rge. (E) (W)27

County Lane Total Depth 2195'

Abandoned Oil Well Gas Well Input Well SWD Well CORE HOLE
D & A ~~X~~

Other well as hereafter indicated CORE HOLE

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Bldg., Wichita, Ks. License No.

Operation Completed: Hour 2:30 AM Day 27 Month 4 Year 1972

The above well was plugged as follows:

315'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 110 Cu. Ft. cement
thru DP from 975' to 650'. Pulled DP to 320' and displaced 30 Cu. Ft. cement thru
DP from 320' to 245'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 5/3/72
WELL NO. 5679-W