

15-101-20034-00-00

Form CP-3
Rev. 6-4-68

KANSAS

af

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1972
04-26-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Anderson Well No. A-1 K-1

Location SW-NE-SE Sec. 23 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 2473'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Bldg., Wichita, Ks License No. _____

Operation Completed: Hour 2:15 PM Day 24 Month 4 Year 1972

The above well was plugged as follows:

299'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 110 Cu. Ft. cement
thru DP from 1000' to 675'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 4-27-72
INV. NO. 5641-u