

P

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-101-19003-00-00

Operator's Full Name G-R-O

Complete Address: 52 Drake, Pueblo, Colorado/

Lease Name Gates Well No. 2

Location CN¹/₄ - ~~SW¹/₄~~ ^{SE¹/₄} Sec. 19 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 4613

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: Well drilled on wrong location. () lost-Hole

Plugging Contractor: Hellar Drilling Company, Incorporated,

Address: 1014 Union Center, Wichita, Kans. License No.

Operation Completed: Hour 1:45PM Day 12 Month 4 Year 1964

The Above well was plugged as follows:

254' -- 8 5/8" Surface pipe, cement circulated with 200 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 270', set plug with 1/2 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls, and 10 Sx. cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

DATE 4-17-64

INV. NO. 8975-W

APR 17 1964
04-17-1964
CONSERVATION DIVISION
Wichita, Kansas

Signed: N. D. Juchals
Well Plugging Supervisor