

15-101-19002-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1964
04-28-1964
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name G-R-O
Complete Address: 52 Drake, Pueblo, Colorado.
Lease Name Gates Well No. A-2
Location CNW-SE Sec. 19 Twp. 16 Rge. 22X(E) (W) 27
County _____ Lane _____ Total Depth 4616
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X
Other well as hereafter indicated: _____
Plugging Contractor: Hellar Drilling Company, Incorporated,
Address: 1014 Union Center, Wichita, Ks. License No. _____
Operation Completed: Hour 6:00PM Day 23 Month 4 Year 1964

The Above well was plugged as follows:

256'--8 5/8" Surface pipe, cement circulated with 190 Sx.
Circulated hole with heavy mud, set plug @ 600' and displaced 25 Sx. cement
thru DP. Heavy mud to 250', set plug with 1/2 sack hulls and displaced 20
Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10
Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 4/29/64
INV. NO. 9052-W