

15-101-19001-00-00

QR

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 1970
CONSERVATION DIVISION
Wichita, Kansas

03-30-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name William F. Roland Estate, c/o R. O. Thompson, Administrator,
Complete Address Chapin Building, Medecine Lodge, Kansas. 67104
Lease Name Gates Well No. 1
Location CSW-SE Sec. 19 Twp. 16 Rge. (E) (W) 27
County Lane Total Depth 4656
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling Company, Incorporated,
Address Box #105, Chase, Kansas. License No. 436
Operation Completed: Hour 10:30 AM Day 23 Month 3 Year 1970

The above well was plugged as follows:

271'--8 5/8" Surface casing, cement circulated with 225 Sx.
4350'--4 1/2" Production casing cemented on bottom with 100 Sx. Top perforations from
4194' to 4199'. No plug back indicated.

Pushed plug to 4100', sanded back to 4050' and set 3 Sx. cement with dump bailer.

Pulled 4 1/2" casing and squeezed well initially with 2 sacks hulls and 11 sacks gel and
followed with 100 Sx. cement from 1200' to 775' then 11 sacks gel from 775' to 335'
and followed with 25 Sx. cement from 335' to 260' then 5 sacks gel from 260' to 40'
and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure--
350#. Final shut-in pressure-100#. (Recovered 659' 4 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

15-101-19001-00-00
3-30-70
INV. NO. 16 60-W