

15-101-20029-00-00

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 31 1972  
CONSERVATION DIVISION  
Wichita, Kansas

01-31-1972

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas,

Lease Name Gates Well No. D-1

Location App: CS/2-NW-NE Sec. 18 Twp. 16 Rge. (E) (W)27

County Lane Total Depth 4575'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Building, Wichita, Kansas License No.       

Operation Completed: Hour 10:00 AM Day 28 Month 1 Year 1972

The above well was plugged as follows:

303'--8 5/8" Surface casing, cement circulated with 275 Sx.  
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 110 Cu. Ft. cement  
thru DP from 950' to 625'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru  
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/3 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols  
Well Plugging Supervisor

DATE 2-1-72  
INV. NO. 5094-W