

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-135-23,584-00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Pickrell Drilling Company, Inc. OPERATORS LICENSE NO. 5123

ADDRESS 110 N. Market, Suite 205 - Wichita, Kansas 67202 PHONE # (316) 262-8427

LEASE (FARM) Taylor "L" WELL NO. 1 WELL LOCATION SW NE NE COUNTY Ness

SEC. 13 TWP. 16S RGE. 25W (#)or(W) TOTAL DEPTH 4519' PLUG BACK TO \_\_\_\_\_

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A X SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 277' KB CEMENTED WITH 165sx SACKS

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD X POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Plugged w/50sx @ 1900', 80sx @ 1140', 40sx @ 690', 40sx @ 300', 10sx @ 40' w/bridge plug, 10sx rathole. Plugged w/60/40 poz, 6% gel plus 1/4# floseal per sx.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes  
(If not, explain) Electric Log was not run.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 10:00 AM on 7-31-91.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Doyle Folkerts PHONE # (316) 793-5742

ADDRESS P.O. Box 1303 - Great Bend, Kansas 67530

PLUGGING CONTRACTOR Company Tools LICENSE NO. 5123

ADDRESS 110 N. Market, Suite 205 - Wichita, KS. 67202 PHONE # (316) 262-8427

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: \_\_\_\_\_

(Operator or Agent)  
C. W. Sebitts, President

DATE: August 12, 1991