

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20953-00-00<sup>01</sup>  
Spot: NESE Sec/Twnshp/Rge: 5-32S-39W  
1962 feet from S Section Line, 660 feet from E Section Line  
Lease Name: YEAGER B Well #: 8  
County: MORTON Total Vertical Depth: 6000 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3087		
CIBP		3862		
CIBP		5407		
SURF	8.625	1726		WITH 675 SX CMT
COND	20	40		WITH 4 SX CMT
DVT		3038		
PROD	5.5	5999	0	WITH 1190 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/20/2012 10:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIEBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1181

Proposed Plugging Method: PUMP 25 SX CMT & 200# HULLS AT 3087'. LET SET & TAG TOC. PUMP 30 SX CMT AT 1750'. 30 SX CMT AT 550'. FILL FROM 40' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/20/2012 3:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMPED 25 SX CMT & 200# HULLS AT 3087'. SDFW. TAGGED TOC @ 2416'. 1ST PLUG AT 1750' WITH 30 SX CMT. 2ND PLUG AT 550' WITH 30 SX CMT. 3RD PLUG FILLED FROM 40' TO SURFACE WITH 5 SX CMT. PUMPED 11 SX CMT INTO 5 1/2" X 8 5/8" ANNULAR SPACE. PRESSURE TO 350 PSI.

Perfs:

Top	Bot	Thru	Comments
5497	5506		
3922	3944		
3147	3167		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR RULE\*\* USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED

MAR - 7 2012

KCC DODGE CITY

Signed

Jack MacLasky  
(TECHNICIAN)

RECEIVED

MAR 12 2012

KCC WICHITA

RAWLZ