

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20162-00-00
Spot: NENENWSE Sec/Twnshp/Rge: 21-14S-10W
2323 feet from S Section Line, 1415 feet from E Section Line
Lease Name: VOPAT A Well #: 6
County: ELLSWORTH Total Vertical Depth: 2940 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2777		
SURF	8.625	265		225 SX
PROD	4.5	2939		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/05/2012 2:30 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK

Witness Type: PARTIAL

Date/Time Plugging Completed: 03/06/2012 10:00 AM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. CIBP HAD BEEN SET PREVIOUSLY, SO QUALITY WELL SERVICE CAPPED IT WITH 4 SX'S CEMENT. PERFORATE AT 1200', 900', AND 315'. RUN TUBING TO 1200' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 900' AND PUMP 35 SX'S, PULL TUBING TO 315' AND ATTEMPT TO CIRCULATE CEMENT TO SURFACE. COULD NOT GET TO CIRCULATE. PULL TUBING OUT AND SHUT DOWN FOR DAY. CAME BACK ON 3-6-12 AND CONNECTED ON TO 4.5" CASING AND PUMPED 100 SX'S--STILL DIDN'T CIRCULATE. RAN 1' TUBING DOWN BACKSIDE OF 4.5" TO 230', AND CIRCULATED 60 SX'S CEMENT TO SURFACE. RAN 1" TUBING DOWN INSIDE 4.5" TO 210' AND CIRCULATED 15 SX'S CEMENT TO SURFACE. PULL TUBING OUT AND TOPPED OFF. CASINGS STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
2901	2904	CSG	
2827	2838	CSG	

Remarks: PIONEER WIRELINE #39126. QUALITY CEMENT #5505.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

Form CP-2/3

✓ 3/14/12

✓

RECEIVED
MAR 12 2012
KCC WICHITA