

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-10800-00-00  
Spot: SESESE Sec/Twnshp/Rge: 29-26S-13W  
324 feet from S Section Line, 339 feet from E Section Line  
Lease Name: MOWBRAY Well #: 1  
County: PRATT Total Vertical Depth: 4486 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	850		WITH 600 SX CMT
PROD 7		4251	1206	WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/01/2012 2:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: RANDY GNIEST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: **TBG DROPPED IN WELL. FISHED ON TBG. UNABLE TO RETRIEVE ALL OF TBG. TBG STUCK. TOP OF TBG FISH @ 2618'. PERFORATE AT 2250'. RUN TBG IN TO 2550' & SPOT 100 SX COMMON CMT W/3% CC. PULL TBG UP HOLE. LET CMT SET. TAG TOC. SHOOT OFF 7" CASING & LAY DOWN. RUN TBG IN TO SPOT PLUGS THROUGH. PLUG AT 880' WITH 20 SX GEL & 75 SX CMT. PLUG AT 400' WITH 75 SX CMT. PLUG AT 60' TO SURFACE.**

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/01/2012 4:50 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

**\*\*TBG DROPPED IN WELL. FISHED ON TBG. UNABLE TO RETRIEVE ALL OF TBG. TBG STUCK. TOP OF TBG FISH @ 2618'.\*\* PERFORATE @ 2600'. RUN TBG IN TO 2600'. SPOT 10 SX GEL & 100 SX COMMON CMT W/3% CC. LET CMT SET. TAG TOC @ 2050'. SPOT PLUGS THROUGH 2 3/8" TBG. 1ST PLUG AT 880' WITH 20 SX GEL & 75 SX CMT. 2ND PLUG AT 413' WITH 75 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT.**

Perfs:


Top	Bot	Thru	Comments
4211	4240		MISSISSIPPIAN

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR\*\* USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01

Signed

  
(TECHNICIAN)

RECEIVED  
MAR - 7 2012  
KCC DODGE CITY

RECEIVED  
MAR 12 2012  
KCC WICHITA

Form CP-21

3/14/12