

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05215-00-01
Spot: NWNENE Sec/Twnshp/Rge: 25-11S-18W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: MARSHALL A Well #: 5
County: ELLIS Total Vertical Depth: 3521 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1266		
PROD	5.5	3504		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/09/2012 10:30 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL CO. Phone: (785) 434-2286

Proposed Plugging Method: Ordered-500 sacks 60/40poz mix 4% gel; 100# hulls
3-12-2012 Ordered 250 sacks 60/40 poz mix 4 % gel; 500 # hulls; 2 bags CC.
Emergency Plug With Rig Over Hole
Milled to 1792; lost hole decided to plug
Old plugging report shows 5.5" CSG was shot off @ 1678'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2012 10:20 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Bowman RIH with tubing to 1775', Quality rigged to tubing & mixed & pumped 50 sxs with 250 # hulls mixed in.
Pulled tubing to 1260', Quality rigged to tubing & pumped 200 sxs with 250 # hulls mixed in .
Lost circulation.
Pulled tubing to 760', Quality rigged to tubing & pumped 50 sxs. No circulation shut down to get more hulls.
Pumped an additional 100 sxs with 500# hulls mixed in. No Circulation
Pulled tubing to 500', Quality rigged to tubing & pumped 100 sxs with 100 # hulls mixed in.
Well went on a vacuum. 1:45 PM Operator decided to leave well set until Monday.
3-12-2012 8:45AM Bowman RIH hole with tubing & tagged cement @ 585' pulled tubing to 568', Quality rigged to tubing & pumped 50 sxs with 3% CC. Left set 30 minutes.
Pulled tubing to 300', Quality rigged to tubing & pumped 85 sxs with 200 # hulls mixed into circulate cement to surface. Pulled tubing topped off hole with 5 sxs. Hole was standing full.


Perfs:

Remarks: QUALITY OIL WELL CEMENTING CO. TICKET # 253 & 469

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN)

CM

MAR 12 2012

RECEIVED
MAR 13 2012
3/14/12
KCC WICHITA
Form CP-2/3