

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21786-00-00
Spot: SWNE Sec/Twnshp/Rge: 12-9S-22W
990 feet from N Section Line, 990 feet from E Section Line
Lease Name: BUSS Well #: 1
County: GRAHAM Total Vertical Depth: 3786 feet

Operator License No.: 3809
Op Name: MEM PARTNERSHIP LP, A GENERAL P
Address: PO BOX 130832
SPRING, TX 77393

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	368	0	
T1	2.5	3781	0	
DVT	5.5	1748		
PROD	5.5	3781	0	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: WILLIAM JACKSON AND/O Company: QUALITY WELL SERVICE, INC. Phone: (936) 828-3018

Proposed Plugging Method: RODS AND TUBING STUCK IN HOLE ABLE TO GET RODS OUT DOWN TO 3125'. COULD NOT RETRIEVE ANY TUBING. PERF AT 3100', 1750', 900' AND 250'. 320 SXS 60/40 POZ 4% GEL.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2012 11:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perf at 3100' pumped 150 sxs cement. Came up the hole and shot another perf at 1750' pumped another 70 sxs cement. Moved up the hole and shot perf at 900' and at 250' then pumped another 100 sxs cement let set overnight. Went back in next day and tagged cement at 180'. Went down the back side with 1' tubing and pumped 30 sxs cement. Then pumped 25 sxs down the 5 1/2 and 20 sxs cement down the tubing.

Perfs:

Top	Bot	Thru	Comments
3780	3786		

Remarks:

Plugged through: TBG

District: 04

Signed *Marvin Mills*

(TECHNICIAN)

RECEIVED

CM

MAR 08 2012

MAR 13 2012 Form CP-2/3
3/14/12
KCC WICHITA