

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20909-00-00
Spot: W2NENW Sec/Twshp/Rge: 29-2S-26W
660 feet from N Section Line, 1650 feet from W Section Line
Lease Name: SHIRLEY TRUST Well #: 1-29
County: DECATUR Total Vertical Depth: 3780 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	275		175 SX
PROD	4.5	3997		110 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2012 12:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (800) 962-1206

Proposed Plugging Method: Ordered 300sx 60/40 pozmix 4% gel cement, 1000# hulls
Plugged through tubing. Casing has holes.

Plugging Proposal Received By: CASE MORRIS WitnessType: PARTIAL
Date/Time Plugging Completed: 02/23/2012 12:40 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Port Collar set @2161 w/325sx. Cement did not circulate. Top of cement @1600'. Operator pumped 120sx down 8/5/8. Cmt void from 1600' to 800'. Sand pump and cable stuck in hole with top of fish @3081'. Perforated @1420. Ran tubing to 2560' and tagged fill up. Pulled tubing to 2528'. Pumped 100sx cmt w/300# hulls. Pulled tubing to 1498'. Pumped 50sx cmt. Cmt to surface. PTOH. Connected to casing and pumped 20sx cmt. 200psi MAX. Connected to 85/8". Immediated pressure to 200 psi.

Perfs:

Top	Bot	Thru	Comments
3704	3706		LKC L
3686	3690		LKC K
3660	3662		LKC J
3592	3596		LKC G
3544	3546		LKC B

Remarks: SWIFT #21411

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

FEB 24 2012

RECEIVED
Form CP-2/3
MAR 13 2012 3/14/12
KCC WICHITA