

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-05360-00-01  
Spot: NENENE Sec/Twnshp/Rge: 7-14S-19W  
330 feet from N Section Line, 330 feet from E Section Line  
Lease Name: VELEY-REIDEL Well #: 1  
County: ELLIS Total Vertical Depth: 3869 feet

Operator License No.: 5798  
Op Name: WEILERT, MICHAEL D. DBA MICHAEL  
Address: 866 230TH AVE  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3869		
SURF	10.75	133		150 SX
PROD	6.625	3837		350 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/07/2012 12:30 PM  
Plug Co. License No.: 34519 Plug Co. Name: DOUBLE DRUM WELL SERVICE LLC  
Proposal Revd. from: CURTIS WEILERT Company: MICHAEL D WEILERT OIL CO. Phone: (785) 656-3540

Proposed Plugging Method: Ordered- 300sxs 60/40 poz mix 4% gel; 300 # hulls  
Operator drilled out of CSG @ 1322' could not get back into pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/07/2012 3:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Double Drum RIH with tubing to 1277' Swift rigged onto tubing & mixed & pumped 200 sxs 60/40 pox mix, with 300 # hulls mixed into circulate cement to pit area.  
Pulled tubing topped off 6.625" CSG with 30 sxs cement. Hole was standing full.  
Checked 10.75" CSG backside was full of cement.

Perfs:

Top	Bot	Thru	Comments
3862	3869		

Remarks: SWIFT SERVICES INC. TICKET # 21432  
Plugged through: TBG

District: 04

Signed   
(TECHNICIAN) CM

MAR 07 2012

RECEIVED Form CP-2/3  
MAR 13 2012 3/14/12  
KCC WICHITA