

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-22904-00-01  
Spot: SESWSW Sec/Twnshp/Rge: 29-25S-11W  
349 feet from S Section Line, 4336 feet from E Section Line  
Lease Name: THOMAS Well #: OWWO-#1  
County: STAFFORD Total Vertical Depth: 4260 feet

Operator License No.: 5046  
Op Name: RAYMOND OIL COMPANY, INC.  
Address: PO BOX 48788  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	264		WITH 250 SX CMT
PROD	4.5	4200	1620	WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/05/2012 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 4000' & 2 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 295' WITH 100 SX CMT. PLUG AT 40' WITH 40 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/05/2012 3:25 PM KCC Agent: RICHARD LACEY

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

SANDED TO 3850' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 604' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 316' WITH 100 SX CMT. 3RD PLUG AT 41' WITH 40 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.  
Plugged through: CSG

RECEIVED  
MAR 19 2012

District: 01 Signed Richard W. Lacey KCC WICHITA  
(TECHNICIAN)

RECEIVED  
MAR 12 2012  
KCC DODGE CITY

Form CP-2/3  
3/21/12