

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-069-20365-00-00  
Spot: S2SESENE Sec/Twnshp/Rge: 16-28S-30W  
2330 feet from N Section Line, 330 feet from E Section Line  
Lease Name: JOSSERAND Well #: 2-16  
County: GRAY Total Vertical Depth: 5380 feet

Operator License No.: 5316  
Op Name: FALCON EXPLORATION, INC.  
Address: 125 N MARKET STE 1252  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1870		WITH 825 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/26/2012 10:00 AM  
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY  
Proposal Rcvd. from: ALAN Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 1900' WITH 50 SX CMT. 2ND PLUG AT 810' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE  
Date/Time Plugging Completed: 02/26/2012 2:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG AT 1900' WITH 50 SX CMT. 2ND PLUG AT 810' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED  
MAR 19 2012  
KCC WICHITA

District: 01

Signed

Steve Durrant  
(TECHNICIAN)

RECEIVED  
MAR - 8 2012  
KCC DODGE CITY

Form CP-2/3

3/21/12