

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21854-00-00
Spot: W2NWNW Sec/Twnshp/Rge: 30-19S-19W
660 feet from N Section Line, 330 feet from W Section Line
Lease Name: SCHENK Well #: 1-30
County: RUSH Total Vertical Depth: 4400 feet

Operator License No.: 34244
Op Name: CORTEZ HEARTLAND, LLC
Address: 3131 MC KINNEY AVE, STE 430
DALLAS, TX 75204

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3824		WITH 2 SX CMT
CIBP		4250		
SURF	8.625	560		WITH 230 SX CMT
DVT		2100		TOC = 1600'
PROD	5.5	4374	1250	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/06/2012 3:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: OZZIE Company: GRESSEL OILFIELD SERVICE, LLC Phone: (316) 524-1225

Proposed Plugging Method: SAND TO 3780' & 2 SX CMT. PLUG AT 1400' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL
Date/Time Plugging Completed: 03/06/2012 7:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3824' WITH 2 SX CMT ON TOP WITH DUMP BAILER. 1ST PLUG AT 1210' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 588' WITH 50 SX CMT. 3RD PLUG AT 80' WITH 60 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4342	4350		
4206	4209		
3970	3980		
3840	3850		
3830	3840		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED
MAR 19 2012
KCC WICHITA

District: 01

RECEIVED

MAR 1 2 2012

KCC DODGE CITY

Signed

Richard M. Lacey

(TECHNICIAN)

3/21/12