

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21331-00-00
Spot: N2SENE Sec/Twnshp/Rge: 34-12S-20W
3630 feet from S Section Line, 660 feet from E Section Line
Lease Name: SCHNELLER Well #: 3
County: ELLIS Total Vertical Depth: 3850 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD. PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3842		
SURF	8.625	289		175 SX
PROD	4.5	3874		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/09/2012 10:30 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE
Proposal Rcvd. from: GARY WAGNER Company: _____ Phone: (785) 625-6374

Proposed Plugging Method: TUBING STUCK @ 3807', UNABLE TO GET BELOW 3558'. DV TOOL @ 1650' W/ 550 SX. ORDERED OUT 350 SX 60/40 POZ-MIX 4 % GEL, W/ 500# HULLS.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/09/2012 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

RAN TUBING TO 3554' T.O.F. @ 3558' ALLIED PUMPED 50 SX 60/40 POZ MIX 4% GEL, PULLED TUBING TO 3014', AND PUMPED 100 SX CEMENT W/ 300# HULLS. PULLED TUBING TO 1632' AND PUMPED 70 SX CEMENT W/ 200# HULLS CIRCULATED CEMENT. P.T.O.H. SQZ'D 40 SX CEMENT DOWN 4 1/2" CASING MAX 300# S.I.P. 300#. HOOKED UP TO BACKSIDE AND PUMPED 10 SX MAX 1000#, S.I.P. 1000#.

Perfs:

Top	Bot	Thru	Comments
3863	3866		
3797	3807		
3670	3674		
3664	3666		
3645	3650		
3621	3626		
3584	3588		
3566	3571		
3502	3507		
3489	3493		

Remarks: ALLIED TICKET # 42416

Plugged through: TBG

RECEIVED
MAR 20 2012
KCC WICHITA

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

MAR 11 2012

Form CP-2/3

3/20/12