

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21072-00-00  
Spot: NENENW Sec/Twnshp/Rge: 31-8S-17W  
4950 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: RUSS Well #: 8  
County: ROOKS Total Vertical Depth: 3382 feet

Operator License No.: 33190  
Op Name: NOBLE ENERGY, INC.  
Address: 1625 BROADWAY, STE 2200  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.25	160		100 SX
PROD	5.5	3381		130 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/05/2012 10:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: JERRY WIRTZ Company: BASIC ENERGY SERVICES, LP Phone: (785) 625-4052

Proposed Plugging Method: Ordered 400 sx 60/40 poz 4% gel cement, 500# hulls

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/05/2012 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3138', stacked out. Pulled tubing to 3123'. Pumped 150 sx cmt w/150# hulls.  
Pulled to 1857'. Pumped 157 sx cmt w/300# hulls. Circulated to surface.  
PTOH. Hooked to 5 1/2 casing. Pumped 25sx cmt. 250 psi. Cement circulated up backside.

Perfs:

Top	Bot	Thru	Comments
3343	3345		
3337	3339		

Remarks: BASIC TICKET #171805246A

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

MAR 12 2012

RECEIVED

MAR 20 2012

Form CP-2/3

3/21/12

KCC WICHITA