

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22298-00-00
Spot: SESWNW Sec/Twnshp/Rge: 20-8S-17W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: STAMPER A Well #: 6
County: ROOKS Total Vertical Depth: 3393 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3239		
SURF	8.625	216		140 SX
PROD	5.5	3389		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2012 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: LENNY M. DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed
Plugging
Method:

As per KCC Agent's instructions. ORDERED OUT 350 SX 60/40 POZMIX 4% GELW/ 500# HULLS.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2012 10:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

SQZ'D @ 900' TO SURFACE, 8/1984. SWIFT SERVICES PUMPED 330SX 60/40 POZ-MIX
4% GEL DOWN 5 1/2" CASING WITH 500# HULLS, MAX PRESSURE 600# S.I.P. 300#.
HOOKED UP TO BACKSIDE & PUMPED 5 SX CEMENT MAX 300# S.I.P. 200#

Perfs:

Top	Bot	Thru	Comments
3325	3330		
3292	3296		
3130	3133		
3087	3090		
2982	2985		

Remarks: SWIFT SERVICES TICKET # 21260

Plugged through: CSG

District: 04

Signed

Richard Williams
(TECHNICIAN)

CM

MAR 19 2012

RECEIVED
MAR 20 2012 3/21/12
Form CP-2/3
KCC WICHITA