

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20255-00-00
Spot: SWNENE Sec/Twnshp/Rge: 36-15S-13W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: SELLENS C Well #: 3
County: RUSSELL Total Vertical Depth: 3634 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	458		250 SX
PROD	5.5	3414		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/27/2012 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 564-2240

Proposed Plugging Method: Ordered 350sx 60/40 4% gel cement, 400# hulls, and 10sx gel

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2012 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated @1450', 850', 430'
Ran tubing to 3200'. Pumped 10sx gel followed by 75sx cmt w/200# hulls.
Pulled tubing to 1500'. Pumped 65sx cmt w/100# hulls.
Pulled tubing to 850'. Pumped 65sx cmt w/100# hulls.
Pulled tubing to 450'. PUMped 50sx cmt. Cement circulated.
PTOH. Tied onto casing and pumped 80sx cmt. Cement circulated up surface pipe.

Perfs:

Top	Bot	Thru	Comments
3371	3376		
3346	3354		

Remarks: COPELAND ACID AND CEMENT

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

RECEIVED
MAR 20 2012
KCC WICHITA

MAR 12 2012

Form CP-2/3

3/21/12