

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-20106-00-00
Spot: NWSWSWSW Sec/Twnshp/Rge: 32-13S-2W
511 feet from S Section Line, 5237 feet from E Section Line
Lease Name: GEIS Well #: 1
County: SALINE Total Vertical Depth: 3665 feet

Operator License No.: 34257
Op Name: KANSAS GEOLOGICAL SURVEY, UNIV
Address: 1930 CONSTANT AVE
LAWRENCE, KS 66047

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	281		100 SX
PROD	7.625	3345		190 SX

Well Type: ST UIC Docket No: _____ Date/Time to Plug: 03/01/2012 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: MIKE DEALY Company: _____ Phone: (316) 943-2343

Proposed Plugging Method: 1) SAND OPEN HOLE BACK INTO 7.625 CASING TO A MINIMUM OF 3295', 2) CAP THE SAND WITH 10 SACKS CEMENT, 3) PEROFRATE 7.625 CASING AT 330' AND CIRCULATE CEMENT ON BACKSIDE FROM 330' TO SURFACE, 4) CEMENT INSIDE 7.625 CASING FROM 330' TO SURFACE, 5) REMOVE CASING FROM 4' TO GROUND LEVEL AND BACKFILL WITH CLEAN COMPACTED SOIL, 6) ALL METHODS, MATERIALS, SUPPLIES AND EQUIPMENT USED TO PLUG THE WELL MUST COMPLY WITH INDUSTRY PLUGGING STANDARDS AND KCC REGULATIONS.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/07/2012 12:00 AM KCC Agent: BRANDON MILNER

Actual Plugging Report:

RIG UP, DIG PITS, SET CIBP @ 3,335' AND PERFORATED @ 330'. RAN IN WITH BAILER AND CAPPED WITH 10 SX. RAN TUBING TO 341' AND PUMPED 140 SX OF 60/40 4% GEL. PULLED TUBING AND PUMPED ANOTHER 70 SX AT SURFACE. CEMENT DID NOT CIRCULATE ON BACKSIDE. RAN 51' OF 1' PVC DOWN BACKSIDE AND TAGGED CEMENT. TOPPED OFF BACKSIDE WITH 20 SX.

Perfs:

Top	Bot	Thru	Comments
3345	3665	OH	OPEN HOLE

RECEIVED
MAR 20 2012

Remarks: QUALITY TICKET #5506, PLUGGED DUE TO 10 YEAR RULE

KCC WICHITA

Plugged through: TBG

District: 02

Signed _____

Brandon Milner

(TECHNICIAN)

3/21/12

SK