

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-24013-00-00
Spot: SENENWSW Sec/Twnshp/Rge: 7-7S-19W
2210 feet from S Section Line, 1225 feet from W Section Line
Lease Name: GASPER Well #: 1-7
County: ROOKS Total Vertical Depth: 3580 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W MAIN PO BOX 428
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212		150sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2012 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: MARK Company: WW DRILLING, LLC Phone: _____

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE
Date/Time Plugging Completed: 03/14/2012 1:00 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st plug @1620 w/25 sx
2nd plug @970 w/100 sx
3rd plug @265 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx

Remarks: SWIFT

Plugged through: DP

RECEIVED
MAR 20 2012
KCC WICHITA

District: 04

Signed Ed Schumacher
(TECHNICIAN)

CM

MAR 15 2012

Form CP-2/3

3/21/12