



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JAN 4 1968

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

December 21, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Art Lamb of Lamb Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Tom Brown

Complete Address: Box 387, Lindsborg, Kansas 67456

Lease Name: Martin Well No. 7

Location: C NW SE Sec. 3 Twp. 16 Rge. 3 (E)(W) X

County: Saline Total Depth 3340' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lamb was instructed to plug the well as follows:


Fill hole with sand to 3250' and cement with 4 sacks.

Fill hole with mud to 260'. Set rock bridge from 260' to 250' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent