



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

July 27, 1963

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Art Lamb of Lamb Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Tom C. Brown

Complete Address: Box 387, Lindsborg, Kansas

Lease Name: Sanderson Sangren JD KCC Well No. 1

Location: NW NW NE Sec. 2 Twp. 16 Rge. 3 (N) (W) X

County Saline Total Depth 3375 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 3250' and cement with 3 sacks.

Fill hole with mud to 300'. Set rock bridge from 300'

to 290' and cement with 25 sacks. Fill hole with mud to

40'. Set rock bridge from 40' to 30' and cap hole with

10 sacks cement.

Very truly yours,


 Conservation Division Agent