

State of Kansas



15-169-00133-00-00

FORM - CP-2
Rev. 9-8-64

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN P. GRAUERHOLZ Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

June 4, 1965

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

STATE CORPORATION COMMISSION

JUN 16 1965

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Kirby Petroleum Company

Complete Address: 402 First Nat'l Bldg., Pawhuska, Oklahoma

Lease Name: Ellen Oleen Well No. 1

Location: C NW SW Sec. 8 Twp. 16 Rge. 3 (E) (W) X

County Saline Total Depth 3445' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3430' and cement with 5 sacks.

Fill hole with mud to 310'. Set rock bridge from 310' to 300' and cement hole with 25 sacks.

Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Robert J. Londerholm
Conservation Division Agent