



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

July 14, 1964 RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Darrel Kelso of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Frank J. Black

Complete Address: Box 150, McPherson, Kansas

Lease Name: Erickson Well No. 1

Location: SW 1/4 SE Sec. 32 Twp. 16 Rge. 3 (W) X

County Saline Total Depth 3435' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

Fill hole with sand to 3420' and cement with 4 sacks.

Fill hole with mud to 210'. Set rock bridge from 210'

to 200' and cement hole with 20 sacks. Fill hole with

mud to 40'. Set rock bridge from 40' to 30' and cap

hole with 10 sacks cement.

Very truly yours,

Wilbur J. Loman
Conservation Division Agent