

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-169-00064-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

July 29, 1966

RECEIVED
AUG 10 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bert Self of Self Casine Pulling Co. has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Tom C. Brown

Complete Address: P.O. Box 387, Lindsborg, Kansas

Lease Name: Allen Nelson Well No. 1

Location: C SW SW Sec. 32 Twp. 16 Rge. 3 (E)(W) X

County Saline Total Depth 3380' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3360' and cement with 5 sacks.

Fill hole with mud to 260'. Set rock bridge from 260' to 250' and cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Arthur J. Loman
Conservation Division Agent