



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
MAY 27 1968
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

May 15, 1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bert Self of Bert Self Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: W-D Oil Company

Complete Address: c/o Bert Self, R. R. # 4, Hutchinson, Kansas

Lease Name: Gibson Well No. 1

Location: SE NE NE Sec. 32 Twp. 16 Rge. 3 (W) X

County: Saline Total Depth 3400' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

- Fill hole with sand to 3375' and cement with 3 sacks.
- Fill hole with mud to 310'. Set rock bridge from 310' to 300' and cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

William J. Johnson
Conservation Division Agent