

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-169-00587-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1974

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Fell & Wolfe Oil Company

Complete Address Box 7447, Tulsa, Oklahoma 74105

Lease Name J. Godfry Oborg Well No. 4

Location C W/2 NE NW Sec. 17 Twp. 16 Rge. 3 (E) (W) X

County Saline Total Depth 3425'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Art Lamb Casing Pulling Co.

Address 2809 King, Hutchinson, Kansas License No. 440

Operation Completed: Hour 5 PM Day 3 Month June Year 1974

The above well was plugged as follows:

Hole filled with sand to 3400' and cemented with 3 sacks cement.

Hole filled with mud to 215'. Rock bridge set from 215' to 200' and hole cemented with 25 sacks cement. Hole filled with mud to 40'.

Rock bridge set from 40' to 30' and hole cemented to base of cellar with 10 sacks cement.

2276' of 4½" casing recovered.

I hereby certify that the above well was plugged as herein stated.

Signed: *Arthur J. Loren*
Well Plugging Supervisor

INVOICED

DATE 6/11/74

INV. NO. 9267-W