

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-169-00586-00-01
RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Fell & Wolfe Oil Company
Complete Address Box 7447, Tulsa, Oklahoma 74105
Lease Name J. Godfrey Oborg Well No. 1
Location C NW NW Sec. 17 Twp. 16 Rge. 3 (E) (W) X
County Saline Total Depth 3464'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Art Lamb Casing Pulling Co.

Address 2809 King, Hutchinson, Kansas License No. 440

Operation Completed: Hour 5 PM Day 12 Month June Year 1974

The above well was plugged as follows:

Hole filled with sand to 3400' and cemented with 3 sacks cement.
Hole filled with mud to 215'. Rock bridge set from 215' to 200' and
hole cemented with 25 sacks cement. Hole filled with mud to 40'.
Rock bridge set from 40' to 30' and hole cemented to base of cellar
with 10 sacks cement.

Recovered 2630' of 4½" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. J. Leland*
Well Plugging Supervisor

INVOICED

DATE 6/21/74

INV. NO. 9339-W