

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Okmar Oil Company

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name North Well No. 1

Location W/2 SW SW Sec. 1 Twp. 16 Rge. (E) (W)25

County Ness Total Depth 4498'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 4:30 P Day 18 Month 9 Year 1973

The above well was plugged as follows:

Total Depth 4498' 8 5/8 csg set at 321' cwc 200 sk.

4 1/2 csg set at 4488' cw 75 sk cmt.

Filled 4 1/2 csg W/sd (4470-4498) dumped 3 sk cmt W/dump bailer. (4435-4470)

Cutoff and recovered 2900' of 4 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/500 lbs hulls--70 sk cmt--10 sk

gel & water, released 8 5/8 plug and pumped 50 sk cmt by HOWCO.

Max. pp 500 lbs. SIP 200 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Len G. Massey
Well Plugging Supervisor

RECORDED

DATE 9-19-73

INV. NO. 7927-10