

15-135-20354-0000

Form CP-3
Rev. 6-4-68

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name Kaler Well No. 3

Location C NE SE Sec. 2 Twp. 16 Rge. (E) (W) 25

County Ness Total Depth 4534

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Strata Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 6:15 P Day 21 Month 7 Year 1970

The above well was plugged as follows:

RTD 4534 8 5/8 csg set at 288' cwc 160 sk Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/24/70
INV. NO. 2281-W

Signed: Ben F. Massey
Well Plugging Supervisor