

15-169-00572-00-01

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15- (none) ✓ R

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name P. R. Oil Properties

Complete Address 100 Laurel Court, McPherson, Kansas 67460

Lease Name H. Johnson "B" Well No. 1

Location NW NW NW Sec. 8 Twp. 16 Rge. 3 (East)(West)

County Saline Total Depth 3145'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Operator and Allied Cementing Co., Inc.

Address 100 Laurel Court, McPherson, Kansas License No. \_\_\_\_\_

Operation Completed: Hour: 1 PM Day: 27 Month: August Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

Pumped 8 sacks gel-mud through tubing on bridge at 1200'. Pumped  
20 sacks 50/50 Permox through tubing @ 1200'. Pulled tubing to 320' and  
pumped 30 sacks 50/50 Permox w/2 gel @ 320'. Pulled  
tubing. Pumped 60 sacks Permox into annulus. Pumped 10 sacks into  
4 1/2" to fill to cellar.

No casing recovered.

Amount of Surface Casing: 8 5/8" - 315' - 250 sacks

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: \_\_\_\_\_  
Conservation Division Agent

INVOICED  
DATE 9-9-82  
INV. NO. 1117-W

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 7 1982  
CONSERVATION DIVISION  
Wichita, Kansas

Salems 609

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Mardock,  
Wichita, Kansas


15-169-00572-00-01  
SEC. 8 T. 16 R. 3W  
NW NW NW

Company PHILLIPS & SANDERSON  
Farm Johnson "B" No. 1

Total Depth 3445  
Curren. 12-8-52 Comp. 12-24-52  
Shot or Treated.  
Contractor E. K. Carey  
Issued 12-26-53

County Saline

KANSAS



Elevation 1351 DF

Production 122 BO, 1% water

CASING:  
8 5/8 @ 315' w/ 250 sx cmt.  
5 1/2 @ 3442' w/ 50 sx cmt.

Figure 1. Waste Pattern of Formations.

cellar	7
shale	30
shale & shells	270
lime	370
lime & shale	550
lime	955
shale & lime	1000
shale & shells	1630
lime	2018
lime & shale	2100
shale & shells	2287
lime	2565
shale & lime	2895
shale	2908
Mississippi lime	2957
lime	3213
shale	3235
shale & lime	3305
shale	3354
lime	3388
shale	3445
Total Depth	

(3 feet open)

TOPS:	
Sand	2909
Mississippi	2922
Base Mi sissippi	2921
Hunton	3368
Maquoketa shale	3381
Maquoketa dolomite	3441

15-169-00572-00-01

Phone 913-483-2627, Russell, Kansas  
 Phone 316-793-5861, Great Bend, Kansas

Phone Plainville 913-434-2812  
 Phone Kiowa 316-825-4618

# ALLIED CEMENTING CO., INC.

Home Office P. O. Box 31      Russell Kansas 67665      No 29196

Date <b>3-27-82</b>	Sec.	Twp.	Range	Called Out <b>5:00 AM</b>	On Location <b>9:30 AM</b>	Job Start <b>10:30</b>	Finish
Lease <b>JOHNSON</b> Well No. <b>B7</b>			Location <b>ASSAR TAIN 3VSS</b>			County <b>SALINE</b>	State <b>KC</b>

Contractor <b>PERA WELL SERV</b>	
Type Job <b>DLD HOLE PLUG</b>	
Hole Size	T.D. <b>3445</b>
Csg. Size <b>5 1/2</b>	Depth
Tbg. Size <b>2"</b>	Depth
Drill Pipe	Depth
Tool	Depth
Cement Left in Csg.	Shoe Joint
Press Max.	Minimum
Meas Line	Displace
Perf.	

Owner	To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.
Charge To	<b>P+R PROPERTIES</b>
Street	<b>PL 11</b>
City	<b>MISSOURI</b> State
The above was done to satisfaction and supervision of owner agent or contractor.	

EQUIPMENT		
No	Cementer	
Pumptrk <b>12 61</b>	Helper	<b>LEON JOHN</b>
No	Cementer	
Pumptrk	Helper	
Bulktrk <b>11 117</b>	Driver	<b>ROGER SEAN</b>
Bulktrk	Driver	

Purchase Order No.	
X <b>PAID</b>	
<b>CEMENT</b>	
Amount Ordered	<b>130 SKS 50/50 POZ</b>
Consisting of	<b>2 0/10 GEL 8 SKS GEL</b>
Common	
Poz. Mix	
Gel.	
Chloride	
Quickset	

DEPTH of Job	
Reference: <b>#</b>	
<b>14 ME</b>	
Sub Total	<b>429.00</b>
Tax	
Total	

Sales Tax	
Handling	<b>16.00</b>
Mileage	<b>1.00</b>
Sub Total	<b>17.00</b>
Total	<b>446.00</b>
Floating Equipment	

Remarks:  
 1 PUMPED 8 SKS GEL 20 SKS CEMENT  
 2 IN AT 1700' 700 PSI AT 320' PUMPED IN  
 30 SKS BACK SIDE 60 SKS 20' GEL  
 10 SKS ON TOP IN 4 1/2 CS.