

15-169-19165-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
APR 23 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Raymond <sup>Oil</sup> Supply Company, Inc.

Complete Address 200 West Douglas, Wichita, Kansas 67202

Lease Name Johnson Well No. B-1

Location C W 1/2 SW SE Sec. 8 Twp. 16 Rge. 3 (E) (W)

County Saline Total Depth 3400'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Company, Inc.

Address Chase, Kansas License No. # 624

Operation Completed: Hour 4 PM Day 20 Month 4 Year 73

The above well was plugged as follows:

8 5/8" - 344' - Circulated w/cement. 5 1/2" - 339 5/2' - Cemented.

Sand to 3380'. 5 Sax. cement at 3380'. Mud to 360'.

Bridge 360' tp 350'. 25 Sax. cement at 350'. Mud to 40'.

Bridge 40' to 30'. 10, Sax. cement 30' to 0.

Pulled 2924' - 5 1/2" - Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/23/73  
INV. NO. 9277-W

Signed: [Signature]  
Well Plugging Supervisor