

15-169-00573-00-01

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-(none) ✓ R

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name P&R Oil Properties

Complete Address 100 Laurel Court, McPherson, Kansas 67460

Lease Name H. Johnson "B" Well No. 2

Location NE NW NW Sec. 8 Twp. 16 Rge. 3 (East)(West)

County Saline Total Depth 275'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated well left open for water well years ago. originally pulled & plugged by Hot Bomb Casing Pulling

Plugging Contractor Operator and Allied Cementing Co, Inc

Address _____ License No. _____

Operation Completed: Hour: 4:00 PM Day: 27 Month: August Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

Run Tubing to 275'. Circulated cement to surface. Pulled tubing and filled hole to base of cellar total 75 sacks 50/50 Perm. w/2% gel.

Did not have any information on surface casing. Can get it off of original plugging record.

Amount of Surface Casing: _____

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

Signed: _____
Conservation Division Agent

SEP 7 1982
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 9-9-82
118-W

15-169-00573-00-01 COP


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company. PHILLIPS & SANDERSON
Farm. H. T. Johnson "B" No. 2

SEC. 8 T. 16 R. 3W
NE NW NW

Total Depth. 3420
Comm. 5-20-53 Comp. 6-10-53
Shot or Treated.
Contractor. E. K. Carey
Issued. 11-7-53

County Saline
KANSAS



Elevation. 1345 FB

Production. Pmp 120 & NW

CASING:

12 1/2" 149' com. w/320 sx
8 5/8" 364 1/8' com. w/238 sx
5 1/2" 3410 1/2' com. w/ 55 sx

Figures indicate Bottom of Formations.

collar	7
shalo	30
sand	36
shab	45
shab & shalls	150
limo & shalo	300
limo	540
limo & shalo	1000
red bed	1020
shalo & limo	3300
limo	2570
shalo & limo	2790
shale & shalls	2888
limo	3210
shalo	3417
limo	3420
Total Depth	

TOFS:

Mississippi	2888
Kinderhook	3184
Hunton	3334
Maquoketa Shale	3356
Maquoketa Dolomite	3417 1/2

Formations K.B.

RECEIVED
STATE CORPORATION COMMISSION
DEC 19 1968
CONSERVATION DIVISION
Wichita, Kansas

15-169-00573-00-01

Phone 913-483-2627, Russell, Kansas
 Phone 316-793-5861, Great Bend, Kansas

Phone Plainville 913-434-2812
 Phone Kiowa 316-825-4618

ALLIED CEMENTING CO., INC.

Home Office P. O. Box 31

Russell, Kansas 67665

No 29198

Date	8-27-82	Sec.		Twp.		Range		Called Out		On Location		Job Start	3:30	Finish	4:00 PM	
Lease	JOHNSON	Well No.	B-2	Location				ASSARIA 3 W 5 S	County	SALINE	State	Ks				
Contractor								Owner								
Type Job								To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cement and helper to assist owner or contractor to do work as listed.								
Hole Size								T.D.								
Csg. Size								Depth								
Tbg. Size								Depth								
Drill Pipe								Depth								
Tool								Depth								
Cement Left in Csg.								Shoe Joint								
Press Max.								Minimum								
Meas Line								Displace								
Perf.								Purchase Order No.								
EQUIPMENT								Charge To: PVR OIL CO. Street: City: State: The above was done to satisfaction and supervision of owner agent or contractor. X <i>[Signature]</i> CEMENT								
Pumptrk								Amount Ordered								
Pumptrk								Consisting of								
Bulktrk								Common								
Bulktrk								Poz. Mix								
								Gel.								
								Chloride								
								Quickset								
								Sales Tax								
DEPTH of Job								Handling								
Reference:								Mileage								
								Sub Total								
								Total								
								Floating Equipment								
Remarks: Circulated cement from 200' job 75 lbs																
<i>Thank you</i>																