

KANSAS

Form CP-3  
Rev. 6-4-68

15-169-00615-00-00

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 5 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Tom C. & Melva Brown

Complete Address Box 387, Lindsborg, Kansas 67456

Lease Name Runbeck Well No. 2

Location NW NW SW Sec. 33 Twp. 16 Rge. 3 (E) (W) X

County Saline Total Depth 3359'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor The Buckeye Corporation

Address 605 South Main, Eldorado, Kansas License No. 687

Operation Completed: Hour 4 PM Day 26 Month July Year 1974

The above well was plugged as follows:

Pipe had collapsed at 2828'. 4 sacks cement dumped on bridge at 2828'.

Hole filled with mud to 220'. Rock bridge set from 220' to 190' and

hole cemented with 25 sacks cement. Hole filled with mud to 40'.

Rock bridge set from 40' to 30' and hole cemented to base of cellar

with 10 sacks cement.

2820' of 4 1/2" casing recovered.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 8/6/74

INV. NO. 9664-W