

KANSAS

15-169-00614-00-00

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Tom C. & Melva Brown

Complete Address Box 387, Lindsborg, Kansas 67456

Lease Name Runbeck Well No. 1

Location C W/2 SW SW Sec. 33 Twp. 16 Rge. 3 (E) (W) X

County Saline Total Depth 3429'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor The Buckeye Corporation

Address 605 South Main, Eldorado, Kansas License No. 687

Operation Completed: Hour 4 PM Day 29 Month July Year 1974

The above well was plugged as follows:

Hole filled with sand to 3300' and cemented with 4 sacks cement.

Hole filled with mud to 220'. Rock bridge set from 220' to 210' and hole cemented with 25 sacks cement. Hole filled with mud to 40'.

Rock bridge set from 40' to 30' and hole cemented to base of cellar with 10 sacks cement.

2765' of 4 1/2" casing recovered.

I hereby certify that the above well was plugged as herein stated.

Signed: *Arthur J. Leonard*
Well Plugging Supervisor

INVOICED

DATE 8/6/74
INV. NO. 9663-W