

15-169-00915-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Saline County, Sec. 3 Twp. 16 Rge. 3 (E) W (W)

Location as "NE/SE/SW" or footage from lines Tom Brown Construction Co.

Lease Owner BURGMEISTER Well No. 1

Lease Name P. O. BOX 387, LINDSBURG, KANSAS

Office Address P. O. BOX 387, LINDSBURG, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed Feb 26 19 50

Application for plugging filed Jan 17 19 67

Application for plugging approved Jan 18 19 67

Plugging commenced Jan 16 19 67

Plugging completed Jan 23 19 67

Reason for abandonment of well or producing formation Lack of production


If a producing well is abandoned, date of last production October 1 19 66

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Maquoketa Dol Depth to top 3304 Bottom 3357 Total Depth of Well 3397 Feet

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|---------------|---------|------|------|-------|--------|------------|
| Maquoketa Dol | Oil | 3304 | 3312 | 5 1/2 | 3312 | 2850 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back to 3300' with gravel and dumped 5 sacks of cement. Shot pipe off at ~~2857.50'~~ 2857.50'. Pulled pipe and mudded hole to 300'. Set rock bridge and dumped 25 sacks of cement. Finished mudding hole and dumped 10 sacks of cement at top.

FEB 26 1967

Conservation Division

Name of Plugging Contractor Bert Self (Additional description is necessary, use BACK of this sheet)
Address Hutchinson, Kans.

STATE OF Kans. COUNTY OF Reno, ss.

Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self
R. R. #4, Hutchinson, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of February, 19 67

My commission expires October 18, 1969

Joseph Self
Notary Public.

15-169-00915-00-00

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock
Wichita, Kansas

COPY

Company - SPAETH BROS.
Farm - Bygmaister No. 2

SEC. 3 T. 16 R. 9W
SE SE NE

Total Depth. 3397
Comm. 2-10-50 Comp. 2-26-50
Shot or Treated.
Contractor. E. K. Carey
Issued. 9-15-51

County. Saline
KANSAS



CASING:
8 5/8" 310' com. w/225 sx
5 1/2" 3312' com. w/50 sx

Elevation. 1309 ft

Production. Pump. 280'

Figures Indicate Bottom of Formations.

| | |
|--------------------|------|
| base & cellar | 8 |
| shale & shells | 195 |
| lime | 260 |
| broken lime | 265 |
| shale & shells | 300 |
| shale | 305 |
| shells | 310 |
| lime & shale | 1550 |
| lime | 1610 |
| lime & shale | 1820 |
| lime | 1900 |
| lime & shale | 2205 |
| lime | 2320 |
| lime & shale | 2555 |
| shale | 2597 |
| shale & shells | 2758 |
| shale | 2839 |
| lime miss. | 2904 |
| lime & shale | 2956 |
| lime | 3086 |
| shale | 3204 |
| lime | 3397 |
| Total Depth | |
| Tops: | |
| Maquoketa Dolomite | 3204 |
| Viola | 3086 |

33 58
300 25
10

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1967
CONSERVATION DIVISION
Wichita, Kansas