


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 2 Twp. 16S Rge. 3 (X) W. (W)
Location as "NE/CNW/SW" or footage from lines C, NW NW SW/4
Lease Owner E. K. Carey, Contractor
Lease Name Emma Johnson Well No. 1
Office Address Box 620, McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed June 19, 19 50
Application for plugging filed Nov. 1, 19 54
Application for plugging approved Nov. 2, 19 54
Plugging commenced Nov. 6, 19 54
Plugging completed Nov. 9, 19 54
Reason for abandonment of well or producing formation Non Productive

If a producing well is abandoned, date of last production October 27, 19 54
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3389 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	318'	None
				5-1/2	2884'	2884'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 5 sacks of cement at 3355'. Shot pipe off at 2884'. Pulled pipe and mudded hole to 200'. Set rock bridge and dumped 20 sacks of cement at 200'. Finished mudding hole and dumped 10 sacks of cement at 35'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kan COUNTY OF Ren, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Norothy Self
R.R. # 4 Unit Chisnolt, Kan.
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 1954

My commission expires August 12, 1957
Norothy Self Notary Public.

PLUGGING
FILE SEC 2 T 16 R 3W
BOOK PAGE 24 1125 34

11-22-54

E. K. Carey et al
Box 620
McPherson, Kansas

Elevation: 1312 K.B.

Casing Record:

Johnson #1
C, NW/4 NW/4 SW/4
Sec. 2-16S-3W
Saline County, Kansas

5-1/2" Head 3373 w/75 sks

Well Commenced: 6-7-50
Well Completed: 6-19-50

Contractor: E. K. Carey, Contractor, Rig #1, Box 620, McPherson, Kansas
Geologist; Bert Dunn of Dunn & Boreing, Denver, Colorado

Figures Indicate Bottom of Formation K. B.

Rotary base and cellar	95
Shale and shells	135
Shale and shells	275
Lime	305
Lime and shale	780
Lime	960
Shale and shells	1700
Lime	1800
Lime and shale	2025
Shale and lime	2120
Shale	2186
Lime	2530
Shale	2600
Shale and lime	2745
Shale	2830
Lime-Miss	2875
Lime	3100
Shale	3242
Lime and shale	3260
Shale	3372
Lime	3381

Geologist Tops:

Kansas City	2186
Base K. C.	2708
T. Miss.	2832 (-1520)
T. Kind.	3080 (-1768)
T. Maquokets Dol.	3312 (-2000)
T. Cherty Dol. Pay	3374 (-2062)

Recommend casing be set 8 ft. off Bottom. BCD.

Cable Tool Record Drilling In

Drilled plug 8' open hole below shoe, filled up 300' with oil in 1 hour.
1000' fillup in 16 hours.
Drilled 3381 - 3390 Lime Medium soft. Showed stains in samples 3381-88,
fill up 1165' in 14 hours.
Took 5 hours swabbing test making 5.4 Bbls. oil per hour.
Acidized with 500 gals. by Dowell, 9-9-50.
Acidized with 2000 gals. by Dowell, 8-2-51.
Making 3 Bbls. oil and 50 bbls. water per day when discontinued
pumping October 26, 1954.

The above ~~Driller's~~ Driller's Log is correct and complete to the best of my knowledge.

SUBSCRIBED AND SWORN to before this 1st day of November, 1954

E. K. CAREY CONTRACTOR

BY Herbert Rhoton
Herbert Rhoton, Superintendent

Ed. [Signature]
NP

My Commission Expires: November 13, 1956.

PLUGGING
WELL SEC. 2-16-3W
BOOK PAGE 74 LINE 34