


STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to:  
 Conservation Division  
 State Corporation Commission  
 212 North Market, Insurance Bldg.  
 Wichita, Kansas

15-169-00912 -00-00  
 WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Saline County. Sec. 2 Twp. 16 Rge. 3 (E) W (W)  
 Location as "NE/CNW/SW" or footage from lines NE SW NW  
 Lease Owner Tom Brown  
 Lease Name Bjorkland Well No. 2  
 Office Address Lindsborg, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
 Date well completed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
 Plugging commenced 12-1-60 19\_\_\_\_  
 Plugging completed 12-3-60 19\_\_\_\_  
 Reason for abandonment of well or producing formation Depleted.  
 If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3385 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	258'	None
				5-1/2"	3382'	2836'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3385' and found it clear.  
 Sanded from 3385' to 3370' and dumped 5 sacks of cement @ 3370' with dump bailer. Pulled 5 1/2" casing. Mudded hole to 240', set 10' rock bridge to 230' and ran 20 sacks of cement @ 230'. Mudded hole to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.  
 PLUGGING COMPLETE.

1-13-1961

Conservation Division  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor KNIGHT KNIGHT CASING PULLING COMPANY  
 Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or ~~(owner)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December, 1960  
Milton J. Volin Notary Public.  
 My commission expires May 20, 1964

