


15-169-19165-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Saline County, Sec. ⁸ 17 Twp. 16 Rge. 3
C W/2 SW SE (#) (W)
Location as "NE/CNW/SEW" or footage from lines
Lease Owner Raymond Oil Co., Inc.
Lease Name Johnson B#1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4/17/73 19
Plugging completed 4/21/73 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Scott
Producing formation Depth to top Bottom Total Depth of Well 3400 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	344	none
				5 1/2"	3395 1/2	2897'

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1973
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 3380' and dumped 5 sacks cement.
Shot pipe at 2924', pulled 97 joints. Bailed hole to 360' and set 10' rock bridge. Ran 25 sacks cement. Mud to 40', 10' rock bridge and dumped 10 sacks cement. Talled pipe.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of April 1973

My commission expires
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975



Margaret Melcher
Notary Public.

15-169-19165-00-08
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


COPY

Company. DeWEESE-SANDERSON OIL CO.
 Farm. Elmer Johnson "B" No. 1

SEC. 8 T. 16 R. 3W
 C W/2 SW SE

Total Depth. 3400'
 Comm. 5-18-61 Comp. 5-25-61
 Shot or Treated.
 Contractor. Melland Drig. Co.
 Issued. 10-21-61

County Saline
 KANSAS



Elevation. 1346' RR

Production. 25 BOPD

CASING:

8 5/8" 344' cem w/200 ex.
 4 1/2" 3395 1/2' cem w/75 ex.

Figures Indicate Bottom of Formations.

surface soil, clay & shale	20
sand	44
clay & shale	75
shale & shells	270
Anhydrite	344
lime	485
lime & shale	1110
shale & shells	1770
lime & shale	1915
shale & lime	2400
lime & shale	2585
shale & lime	2889
Mississippi Lime	3155
shale & lime	3200
shale	3396
Maquoketa	3400 RTD
Total Depth	
TOPS: SCOUT	
Mississippi	2888
Kinderhook	3154
Maquoketa Dolomite	3396

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 17 1963
 CONSERVATION DIVISION
 Wichita, Kansas